

EXHIBIT 3

Modified Page 5 of 15
NDEP Working in Waterways Permit TNEV2010434

Addendum No. 2
Glendale Water Supply Improvement Project
Contract No. 0910-181

Nevada, the operations shall be conducted in accordance with the plans, information, and specifications submitted to NDEP, and the following terms and conditions:

- a. Any heavy equipment, to be used in the drainages must be thoroughly steam cleaned before being introduced into or work is conducted in the drainages and adjacent wetlands areas to prevent potential contamination. All equipment shall be inspected for leaks daily prior to use.
- b. BMPs shall be applied and precautions shall be taken to minimize erosion and sediment transport at the clearing, grubbing, diversion channel construction, and channel backfilling and grading sites in accordance with plans and information submitted to NDEP prior to commencement of working in waterways.
- c. A record shall be kept of each day's use of heavy equipment in the River, and adjacent areas at the project site.
- d. Any diversion structure shall be engineered to effectively divert water around the project, minimizing seep water. When possible, activities shall be scheduled during periods of low flow.
- e. Every precaution shall be taken to minimize vegetation disturbance or removal as applicable and practicable.
- f. The permittee, **Truckee Meadows Water Authority**, bears the sole responsibility to ensure that the requirements of this temporary permit are fully satisfied.
- g. Equipment fueling and fuel storage areas shall occur at least 200 feet away from the River, as feasible. If the aforementioned occur within the buffer, primary and secondary BMPs shall be implemented to prevent any release of pollutants to the River or ground. Said BMPs shall be detailed in the submitted river diversion and construction water management plan.
- h. Stockpiles and debris shall not be stored near water ways.
- i. All rock to be used in the River must be cleaned (free of particulates < 1/8 inch in diameter) prior to being brought to the site and placed.
- j. No petroleum products, chemicals or foreign debris of any kind shall be discharged or deposited into the River.
- k. **All turbidity sampling results shall be recorded in a log and submitted monthly with DMRs; exceedances above the water quality standard of 10 NTU shall be recorded in the same log book, but also submitted weekly to the Division.**

I.A.5. **Documentation:** Documentation must be submitted as specified in Part I.A.2.

I.A.6. **Final Report:** The final narrative report with photos describing and documenting the results of the project's activities shall be submitted after the end of the permit. The report shall contain the original signature of the Engineer-In-Charge of the project. **The final report shall be received, at the address given below, by the 28th day of the month following project completion or permit expiration, whichever comes first.**

**Nevada Division of Environmental Protection
Bureau of Water Pollution Control
ATTN: Compliance Coordinator
901 South Stewart Street, Suite 4001
Carson City, Nevada 89701-5249**