

Addendum No. 2

2010-2011 Fleisch Flume Rehabilitation

Contract No. 1011-135

October 9, 2010

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

Make the following Change to the Plans Figure 1/3:

Key item B in Table 2 on Figure 1/3 calls for 8 ft wide rolls of PVC liner material inside the flume box. 7-ft wide liner is also acceptable. Note that if 7-ft wide liner material is used and overlapped 6" in the center of the box, it will only come 18" up the wall, not 2-ft as shown on the drawing.

End of Addendum No. 2