

Addendum No. 2

Lewis St., Gould St., Prosperity St., & W. First St.

Main Replacements

TMWA Project #04-201

Bid # 1011-175
December 29, 2010

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

1. Please replace Part 1.07 of Technical Specification Section 01030, Special Provisions, Page 2 with the following:

1.07 SEQUENCING OF MAIN INSTALLATION

Contractor shall coordinate sequencing of main installation with TMWA inspector and TMWA Project Representative prior to construction. In an effort to meet RTC's proposed street rehabilitation schedules and coordinate with the City of Reno Sanitary Division's proposed sewer rehabilitation project, Contractor shall be prepared to begin work in either W. First Street or Lewis Street. Temporary flush assemblies will be required to be installed with NO DIRECT PAYMENT to the Contractor. Main installation sequencing shall be planned to minimize disruption of service to TMWA customers.

2. Please include the following revision to Work Task #9 on Sheet P2 of the Improvement Plans:

INSTALL TEMPORARY FLUSH ASSEMBLY FOR FLUSHING AND TESTING OF WEST SEGMENT NEW WATER MAIN (NO DIRECT PAYMENT)

INSTALL: 6" 8" x 2"Ø FIP TAPPED MJ CAP WITH MECHANICAL JOINT WEDGE ACTION RESTRAINT GLAND

2"Ø MIP x 2"Ø MIP CORPORATION STOP FOR FLUSHING AND TESTING

3. Please include the following revision to Work Task #13 on Sheet P2 of the Improvement Plans:

INSTALL TEMPORARY FLUSH ASSEMBLY FOR FLUSHING AND TESTING OF EAST SEGMENT NEW WATER MAIN (NO DIRECT PAYMENT)

INSTALL: 6" 8" x 2"Ø FIP TAPPED MJ CAP WITH MECHANICAL JOINT WEDGE ACTION RESTRAINT GLAND

2"Ø MIP x 2"Ø MIP CORPORATION STOP FOR FLUSHING AND TESTING

End of Addendum No. 2