

Addendum No. 2

Highland Avenue Main Replacement

TMWA Project #04-204

Bid # 1011-215
March 31, 2011

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

1. The print implies that the existing pipe on Valley Road is Transite Pipe (labeled 8" Tr). The bid item description for the Valley Road connection implies that it is cast iron. Is the existing pipe transite or cast iron pipe?

Sheet PP3 is correct, and the description for Bid Item 3 is incorrect; the connection in Valley Road is to an existing transite main, not cast iron.

2. With the valves being removed at the intersection of Highland and Valley, it appears there are several hundred feet of existing line that will be shut down to perform this work. This will shut down the services for several apartments, businesses and residents. Technical specification 1030, paragraph 1.19 discusses outages but does not specify when this shut down should be performed. Are there specific time constraints for the shut down of this section? Will night or weekend work be required?

No, night and weekend work is not expected. Property owners will be notified in advance of the shut-down.

3. Should a gate valve be added at or near the temporary flush valve at Evans in order to prevent shutting down services for the final connection at Evans?

Yes, a permanent 8" FLXFL gate valve will be required upstream of the temporary flush assembly. This will require a flanged 90-degree elbow turning south, and a simple temporary flush without the 4" gate valve and thrust anchors. Remove the temporary flush and replace with a FLXMJ adapter with MegaLug to complete the tie-in.

Thank you for bringing these items to my attention.

End of Addendum No. 1