

Bid Tabulation Report - DOUBLE DIAMOND TANK 1 ALTITUDE VALVE INSTALLATION

Bids Opened: April 17, 2017

TMWA BID NO.: 2017-008

			Bidder No. 1		Bidder No. 2	
			Gerhardt & Berry Constuction Inc		John Longo Construction Inc	
Bonding Provided			Yes		Yes	
Bidder Acknowledges Receipt of Addendums			Yes		Yes	
Affadivit of Preferential Bidders Status / Bidder's Preference Certificate			N/A <\$250,000		N/A <\$250,000	
Description	Scheduled Value	Unit	Unit Price	Total Price	Unit Price	Total Price
1.1 MOBILIZATION AND DEMOBILIZATION. Mobilization, Insurance, Bonds, Permits, Site Prep, Site Clean-Up, Demoblization, and Miscellaneous Fees	1	LS	\$7,046.00	\$7,046.00	\$10,000.00	\$10,000.00
2.1 CONNECTION TO EXISTING 24" FEEDER MAIN. Includes all labor, equipment, and materials required to cut and dispose existing 24" PVC feeder main and install new 24" DI pipe, 2-24"x16" DI tee's, 24" butterfly valve, 2-16" gate valves, 16" DI pipe, and 16" DI elbows; and 1.5" drain line at the double Diamond Tank 1 site. This item does not include vault and vault accessories; interior mechanical piping and equipment; solar electrical system; and controls system.	1	LS	\$88,924.00	\$88,924.00	\$90,000.00	\$90,000.00
2.2 ALTITUDE VALVE, VAULT, PIPING, AND MECHANICAL. Includes all labor, equipment, and materials required to install new 16" altitude valve at the double Diamond Tank 1 site adjacent to the existing 24" feeder main. Materials include but not limited to: 16" altitude valve with solenoid operated override; pre-cast concrete vault with access hatch and ladder assembly; ball valves, 16" flanged fusion epoxy lined and coated steel pipe spools, saddle tap, etc.This item does not include piping and equipment outside vault; solar electrical system; and controls system.	1	LS	\$95,251.00	\$95,251.00	\$111,000.00	\$111,000.00
2.3 TANK SOLAR/BATTERY ELECTRICAL AND CONTROLS SYSTEM. This item includes all labor, equipment, and materials required to improve the existing solar panel and battery system at the Double Diamond Tank 1 Site. Installation of TMWA and contractor supplied equipment and materials; includes electric/controls panel, conduit, wire etc. This item also includes re-connection of existing tank level transducer, power, and all other incidental electrical work critical to the operation of the solar powered system. This item does not include furnishing TMWA supplied equipment per contract drawings.	1	LS	\$25,114.00	\$25,114.00	\$7,550.00	\$7,550.00
2.4 SWPPP DEVELOPMENT & SITE EROSION CONTROL (BMP'S). Includes all labor, equipment, and materials required to comply with all of the requirements of the construction activity statewide general permit in the vicinity of the Double Diamond 1 Tank site. This item shall also include all soil seeding and revegetation requirements, temporary erosion control measures, sediment barriers, temporary project fencing, slope protection, dust abatement, erosion control requirements, and site cleanliness.	1	LS	\$1,378.00	\$1,378.00	\$5,000.00	\$5,000.00
3.1 ROCK EXCAVATION. Incudes all labor and equipment required for rock removal if encountered.	60	CY	\$52.00	\$3,120.00	\$100.00	\$6,000.00
Total Bid Price			\$220,833.00		\$229,550.00	
Total Bid Price Written in Words? y/n			Yes		Yes	
Bidder Information Provided			Yes		Yes	
Licensing Information Provided			Yes		Yes	
Disclosure of Principals Provided			Yes		Yes	
Referenced Provided			Yes		Yes	
Debarment & Safety Information Provided			Yes		Yes	
Subcontractors Listed / Self Listed			Yes		Yes	
Proposal Summary Executed			Yes		Yes	