

1355 Capital Blvd. • P.O. Box 30013 • Reno, NV 89520-3013
P 775.834.8080 • F 775.834.8003

Addendum No. 1

8" Water Main Replacement for Matterhorn Blvd.

PWP Bid No. WA-2015-195
June 8, 2015

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

QUESTIONS AND RESPONSES

Question No. 1: I'm contacting you in reference to the Matterhorn Boulevard Water Main project and I was trying to determine the installation method and underground depth of the 8 inch pvc pipe being installed in the project?

Response to Question No. 1: Pursuant to Detail 10L-6 on sheet D1 of the bid plan set, and TMWA specifications, minimum depth of cover for the new water main is 36-inches from finish grade. See profile sheets for further information.

In regards to installation method, TMWA is not dictating pipe installation means and methods for this project as long as it complies with pipe manufacturer's recommendations and requirements of the bid documents.

Question No. 2: Can you tell me what the engineers estimate for the above reference project is?

Response to Question No. 2: Range for engineer's estimate is \$200,000 to \$250,000, as noted in the Invitation to Bid advertisement.