

Bid Tabulation Report - 2015 Pressure Regulator Station Rehabilitations

TMWA Bid No. 2016-004

Bids Opened: 9/24/15

			Bidder No. 1		Bidder No. 2	
			John Longo Construction, Co., Inc.		Gerhardt & Berry Construction, Inc.	
Bonding Provided			Yes		Yes	
Bidder Acknowledges Receipt of Addendums			Yes		Yes	
Affidavit of Preferential Bidders Status / Bidder's Preference Certificate			N/A		N/A	
Description	Scheduled	Unit	Unit	Total	Unit	Total
	Value		Price	Price	Price	Price
G-1 MOBILIZATION/DEMOBILIZATION INCLUDING, BUT NOT LIMITED TO, INSURANCE, BONDS, PERMITS, SUBMITTALS, EXISTING SITE DOCUMENTATION, SITE CLEAN-UP ETC..	1	LS	5,000.00	5,000.00	11,476.00	11,476.00
G-2 FURNISH AND INSTALL TRAFFIC CONTROL AT FIFTEEN (15) SITES THROUGHOUT CITY OF RENO.	1	LS	6,500.00	6,500.00	25,168.00	25,168.00
PRS-1C BELFORD 1 PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	2,360.00	2,360.00
PRS-1P BELFORD 1 PRS INTERNAL PIPING MODIFICATIONS INCLUDING BUT NOT LIMITED TO: DEMOLITION OF EXISTING 1" OUTLET, INSTALLATION OF NEW 2" OUTLET, DEMOLITION OF EXISTING 6" FLANGED COUPLING ADAPTER AND 2-6" BUTTERFLY VALVES, INSTALLATION OF 2-6" GATE VALVES WITH HANDWHEELS.	1	LS	5,200.00	5,200.00	5,363.00	5,363.00
PRS-2C BELFORD 2 PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	2,000.00	2,000.00	1,827.00	1,827.00
PRS-2P BELFORD 2 PRS INTERNAL PIPING MODIFICATIONS INCLUDING BUT NOT LIMITED TO: DEMOLITION OF TWO EXISTING 3/4" OUTLETS, AND INSTALLATION OF TWO NEW 1.5" OUTLETS WITH SERVICE SADDLES.	1	LS	1,500.00	1,500.00	543.00	543.00
PRS-3C FOLSOM PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	2,000.00	2,000.00	2,542.00	2,542.00
PRS-4C MERIDIAN PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	1,000.00	1,000.00	3,308.00	3,308.00
PRS-4P MERIDIAN PRS INTERNAL PIPING MODIFICATIONS INCLUDING BUT NOT LIMITED TO: DEMOLITION OF TWO EXISTING 3/4" OUTLETS AND FITTINGS/VALVES, AND INSTALLATION OF NEW OUTLETS.	1	LS	1,500.00	1,500.00	465.00	465.00
PRS-5C MOANA 1 PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND APPLICATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	2,051.00	2,051.00
PRS-5V MOANA 1 PRS SPRAY FOAM INSTALLATION ON STEEL HATCH AND CONCRETE VAULT INTERIOR.	1	LS	1,500.00	1,500.00	3,877.00	3,877.00
PRS-6C MOANA 2 PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	1,998.00	1,998.00
PRS-6V MOANA 2 PRS SPRAY FOAM INSTALLATION ON STEEL HATCH AND CONCRETE VAULT INTERIOR, AND DISPOSAL OF EXISTING INSULATION BLANKET	1	LS	1,500.00	1,500.00	3,877.00	3,877.00
PRS-7C TILLAMOOK PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	2,000.00	2,000.00	2,371.00	2,371.00
PRS-8C MUELLER PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	2,000.00	2,000.00	1,850.00	1,850.00
PRS-9C DRISCOLL BYPASS PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC AND INSTALLATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	1,850.00	1,850.00
PRS-9P DRISCOLL BYPASS PRS INTERNAL PIPING MODIFICATIONS INCLUDING, BUT NOT LIMITED TO, INSTALLATION OF DIELECTRIC BUSHINGS ON TWO EXISTING OUTLETS, CUTTING EXISTING DUCTILE IRON PIPE TO ACCOMMODATE INSTALLATION OF TWO INSULATING FLANGE GASKET KITS AND STEEL FILLER FLANGE, REPLACEMENT OF T-HEAD BOLTS ON 6" FLANGE COUPLING ADAPTER.	1	LS	3,500.00	3,500.00	2,244.00	2,244.00
PRS-10C HEATHERIDGE PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC AND INSTALLATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	4,210.00	4,210.00
PRS-10P HEATHERIDGE PRS INTERNAL PIPING MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: DEMOLITION OF 2 EXISTING 3/4" OUTLETS, INSTALLATION OF 2 - 1.5" OUTLETS, AND REMOVAL OF EXISTING GROUT AROUND WALL PENETRATIONS, CUTTING OF 8" STEEL PIPING, INSTALLATION OF 8" GATE VALVE, 8" LUG BUTTERFLY VALVE, AND RESTRAINED FLANGE COUPLING ADAPTER.	1	LS	6,500.00	6,500.00	5,357.00	5,357.00

Bid Tabulation Report - 2015 Pressure Regulator Station Rehabilitations

TMWA Bid No. 2016-004

Bids Opened: 9/24/15

			Bidder No. 1		Bidder No. 2	
			John Longo Construction, Co., Inc.		Gerhardt & Berry Construction, Inc.	
PRs-11C CRANBROOK PRS INTERNAL PIPING COATING AND PIPING MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, INSTALLATION OF OUTER WRAP, AND REMOVAL OF EXISTING PRESSURE GAUGES AND INSTALLATION OF PIPE PLUGS.	1	LS	1,500.00	1,500.00	2,281.00	2,281.00
PRs-11V CRANBROOK PRS VAULT MODIFICATIONS INCLUDING BUT NOT LIMITED TO: DEMOLITION OF EXISTING HATCH AND GRADE RING, INSTALLATION OF NEW POURED IN PLACE COLLAR, INSTALLATION OF NEW HATCH AND DRAIN LINE, SURFACE AND LANDSCAPE RESTORATION AND RE-ATTACHMENT OF EXISTING LADDER TO POURED IN PLACE CONCRETE COLLAR.	1	LS	3,500.00	3,500.00	4,906.00	4,906.00
PRs-11CG CRANBROOK CURB AND GUTTER DEMOLITION AND REPLACEMENT INCLUDING, BUT NOT LIMITED TO: APPROX. 4' DEMOLITION OF EXISTING CURB AND GUTTER, INSTALLATION OF APPROX. 4' OF NEW CURB AND GUTTER.	4	LF	125.00	500.00	156.00	624.00
PRs-12D MARKRIDGE 1 BYPASS PRS MANHOLE DEMOLITION INCLUDING, BUT NOT LIMITED TO: EXCAVATION AND REMOVAL OF ~35' OF EXISTING 6" STEEL PIPE, DEMOLITION OF EXISTING 6" HOT TAP, DEMOLITION OF EXISTING TAPPING VALVE, INSTALLATION OF BLIND FLANGE AND THRUST BLOCK ON EXISTING VALVE TO BE ABANDONED IN PLACE, EXCAVATION AND REMOVAL OF EXISTING 48" ECCENTRIC MANHOLE/BARREL SECTIONS, AND BACKFILL OF EXCAVATION W/ TYPE 2 AB.	1	LS	10,000.00	10,000.00	6,057.00	6,057.00
PRs-12PV MARKRIDGE 1 BYPASS PRS 3" TEMPORARY PAVEMENT PATCH	400	SQ. FT.	5.00	2,000.00	3.05	1,220.00
PRs-12E MARKRIDGE 1 12" IN-LINE GATE VALVE ADDITION: INSTALLATION OF ~2' - 12" DUCTILE IRON PIPE, INSTALLATION OF 12" FLGxMJ GATE VALVE W/ FCA, INSTALLATION OF 12" TRANSITION COUPLING.	1	LS	9,000.00	9,000.00	8,102.00	8,102.00
PRs-12PD MARKRIDGE 1 BYPASS PRS INTERNAL PUMP STATION PIPING DEMOLITION INCLUDING BUT NOT LIMITED TO: REMOVAL OF ~7.5' OF 8" STEEL, SALVAGING OF 6" PRESSURE REGULATING VALVE, REMOVAL AND DISPOSAL OF TWO EXISTING 8" BUTTERFLY VALVES, REMOVAL OF EXISTING 8" FLANGED COUPLING ADAPTER AND TWO (2) WELDED 8"x6" REDUCERS	1	LS	6,000.00	6,000.00	2,156.00	2,156.00
PRs-12P MARKRIDGE 1 BYPASS PRS INTERNAL PUMP STATION PIPING MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: INSTALLATION OF ~7' OF 8" FABRICATED STEEL PIPING, INSTALLATION OF TWO (2) 8" LUG BUTTERFLY VALVES, INSTALLATION OF 8" PRESSURE REGULATING VALVE, INSTALLATION OF 8" FCA, ~ 14.5' OF 3" Ø FABRICATED STEEL, INSTALLATION OF TWO 3" GATE VALVES, INSTALLATION OF 3" PRESSURE REGULATING VALVE, INSTALLATION OF 1" COMBINATION AIR VALVE, INSTALLATION OF TWO (2) FLANGED COUPLING ADAPTERS, INSTALLATION OF 1" Ø PVC VENT LINE FOR COMBINATION AIR VALVE, RE-INSTALLATION OF PIPE SUPPORT STAND, INSTALLATION OF 3 CEILING CLEVIS HANGERS.	1	LS	42,000.00	42,000.00	34,153.00	34,153.00
PRs-13C HIGHLANDS PRS INTERNAL PIPING COATING MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC AND INSTALLATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	2,266.00	2,266.00
PRs-13D HIGHLANDS PRS INTERNAL PIPING DEMOLITION AND VAULT MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: DEMOLITION AND REMOVAL OF ~11' OF 2" STEEL PIPING, DEMOLITION OF EXISTING 8" BUTTERFLY VALVES, CUTTING OF 6" STEEL PIPING, AND DEMOLITION OF EXISTING FCA. DEMOLITION AND REMOVAL OF 2- 2" GATE VALVES, SALVAGING OF 2" THREADED PRESSURE REGULATING VALVE, VAULT WALL PENETRATION DEMOLITION, INSTALLATION OF PIPE WRAP AND GROUT PLACEMENT, AND CORE DRILLING OF SUMP.	1	LS	6,000.00	6,000.00	2,574.00	2,574.00
PRs-13P HIGHLANDS PRS INTERNAL PIPING MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: INSTALLATION OF 6" FLANGED COUPLING ADAPTER, 2-8" GATE VALVES, 2" OUTLET WITH SERVICE SADDLE, ~11' 2" COPPER PIPING, INSTALLATION OF TWO (2) 2" BRONZE BALL VALVES, REINSTALLATION OF 2" THREADED PRESSURE REGULATING VALVE, INSTALLATION OF TWO (2) - 2" UNIONS DEMOLITION OF TWO (2) EXISTING 1" OUTLETS AND INSTALLATION OF NEW 1.5" OUTLETS.	1	LS	9,000.00	9,000.00	7,992.00	7,992.00
PRs-14C CASHILL PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	2,915.00	2,915.00
PRs-14P CASHILL PRS INTERNAL PIPING AND VAULT MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: DEMOLITION OF ONE (1) EXISTING 3/4" OUTLET, INSTALLATION OF TWO (2) - 1.5" OUTLETS VAULT.	1	LS	1,500.00	1,500.00	1,522.00	1,522.00
PRs-14M CASHILL PRS CONCRETE MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: DEMOLITION OF EXISTING MANHOLE COLLAR AND GRADE RING, INSTALLATION OF NEW POURED IN PLACE COLLAR, RE-INSTALLATION OF EXISTING MANHOLE FRAME AND COVER, WALL PENETRATIONS, AND CEILING REBAR AND CONCRETE REPAIR.	1	LS	3,500.00	3,500.00	2,664.00	2,664.00
PRs-15C SKYLINE PRS INTERNAL PIPING COATING INCLUDING, BUT NOT LIMITED TO: REMOVAL OF DEBRIS FROM PIPE, REMOVAL OF LOOSE PAINT, CLEANING OF PIPE, APPLICATION OF PRIMER AND WAX TAPE, APPLICATION OF MASTIC, AND INSTALLATION OF OUTER WRAP.	1	LS	1,500.00	1,500.00	2,246.00	2,246.00

Bid Tabulation Report - 2015 Pressure Regulator Station Rehabilitations

TMWA Bid No. 2016-004

Bids Opened: 9/24/15

			Bidder No. 1		Bidder No. 2	
			John Longo Construction, Co., Inc.		Gerhardt & Berry Construction, Inc.	
PRS-15P SKYLINE PRS INTERNAL PIPING MODIFICATIONS INCLUDING, BUT NOT LIMITED TO: DEMOLITION OF 2-6" BUTTERFLY VALVES, 1-6" FLANGED COUPLING ADAPTER, AND CUTTING OF 6" PIPING. INSTALLATION OF 2-6" GATE VALVES AND 1-6" RESTRAINED FLANGED COUPLING ADAPTER.	1	LS	6,000.00	6,000.00	4,906.00	4,906.00
Total Bid Price			\$154,200.00		\$169,321.00	
Total Bid Price Written in Words? y/n			Yes		Yes	
Bidder Information Provided			Yes		Yes	
Licensing Information Provided			Yes		Yes	
Disclosure of Principals Provided			Yes		Yes	
References Provided			Yes		Yes	
Debarment & Safety Information Provided			Yes		Yes	
Subcontractors Listed / Self Listed			Yes		Yes	
Proposal Summary Executed			Yes		Yes	