PWP NO.: WA-2016-091

Bid Tabulation Report - North Virginia Street - 18" North Valleys Integration Main

Bids Opened: February 25, 2016

			Bidder No. 1		Bidder No. 2		Bidder No. 3		Bidder No. 4		Bidder No. 5		Bidder No. 6	
			Sierra Nevada Construction, Inc.		**Spanish Springs Construction, Inc.**		**Gerhardt & Berry Construction, Inc.**		**Aspen Developers Corp**		**Q&D Construction Inc.**		**Schauer Excavation, Inc.**	
Bonding Provided			Yes		Yes		Yes		Yes		Yes		Yes	
Bidder Acknowledges Receipt of Addendums			Yes		Yes		Yes		Yes		Yes		Yes	
Affadivit of Preferential Bidders Status / Bidder's Preference Certificate			Yes		Yes		Yes		Yes		Yes		Yes	
Description	Scheduled		Unit	Total	Unit	Total	Unit	Total	Unit	Total	Unit	Total	Unit	Total
	Value	Unit	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price	Price
1. Project Mobilization - including bonds, submittal preparation and coordination, material/product compliance certifications, necessary permitting and general overall project management.	1	LS	26,422.00	26,422.00	22,064.00	22,064.00	80,897.00	80,897.00	97,000.00	97,000.00	192,260.00	192,260.00	70,000.00	70,000.00
2. 18-in CL 200 Polywrapped and Cathodically Protected Ductile Iron Pipe w/restrained joints. Including all saw cutting, excavation, off-haul, bedding, backfill, temporary and permanent asphalt patching, concrete curb & gutter and sidewalk replacement and traffic control as necessary for a complete in-place installation.	424	LF	300.00	127,200.00	350.00	148,400.00	358.60	152,046.40	224.05	94,997.20	275.00	116,600.00	425.00	180,200.00
3. 18-in CL 200 Polywrapped and Cathodically Protected Ductile Iron Pipe w/non-restrained joints. Including all saw cutting, excavation, off-haul, bedding, backfill, temporary and permanent asphalt patching, concrete curb & gutter and sidewalk replacement and traffic control as necessary for a complete in-place installation.	2129	LF	165.00	351,285.00	220.00	468,380.00	200.50	426,864.50	216.06	459,991.74	160.00	340,640.00	249.00	530,121.00
4. Flush Assembly. Complete in-place at the locations shown on the Drawings and per Detail 2/WD2.	1	EA	43,000.00	43,000.00	35,000.00	35,000.00	34,391.00	34,391.00	6,000.00	6,000.00	36,000.00	36,000.00	35,000.00	35,000.00
5. Air/Vac Valve Assembly. Complete in-place at the locations shown on the Drawings and per Detail 1/WD2.	2	EA	13,300.00	26,600.00	12,000.00	24,000.00	11,290.00	22,580.00	6,000.00	12,000.00	15,000.00	30,000.00	9,500.00	19,000.00
6. Connection Detail 4/WD1. Complete and in-place.	1	EA	7,000.00	7,000.00	7,000.00	7,000.00	7,292.00	7,292.00	9,000.00	9,000.00	20,000.00	20,000.00	2,800.00	2,800.00
7. Connection Detail 5/WD1. Complete and in-place.	1	EA	5,500.00	5,500.00	6,000.00	6,000.00	3,888.00	3,888.00	4,500.00	4,500.00	6,000.00	6,000.00	1,700.00	1,700.00
8. 2-inch grind and overlay of asphalt road surfaces as required by the City of Reno SCOA and as indicated on the Drawings.	14000	SF	2.50	35,000.00	2.40	33,600.00	2.05	28,700.00	3.93	55,020.00	4.25	59,500.00	2.50	35,000.00
9. Demobilization and clean-up of staging areas, general construction debris, replacement and/or repair of all damages caused by construction operations related to the Work.	1	LS	1,000.00	1,000.00	3,000.00	3,000.00	1,642.00	1,642.00	36,875.00	36,875.00	5,000.00	5,000.00	15,000.00	15,000.00
Total Bid Price				**$623,007.00**		**$747,444.00**		**$758,300.90**		**$775,383.94**		**$806,000.00**		**$888,821.00**
Bid Amount Discrepancies			None		None		None		Bid Amt $775,375.00	TMWA Total $775,383.94	Bid Amount $804,000.00	TMWA Total $806,000.00	None	
Total Bid Price Written in Words? y/n			Yes		Yes		Yes		Yes		Yes		Yes	
Bidder Information Provided			Yes		Yes		Yes		Yes		Yes		Yes	
Licensing Information Provided			Yes		Yes		Yes		Yes		Yes		Yes	
Disclosure of Principals Provided			Yes		Yes		Yes		Yes		Yes		Yes	
Referenced Provided			Yes		Yes		Yes		Yes		Yes		Yes	
Debarment & Safety Information Provided			Yes		Yes		Yes		Yes		Yes		Yes	
Subcontractors Listed / Self Listed			Yes		Yes		Yes		Yes		Yes		5%=Yes -- 1%=No	
Proposal Summary Executed			Yes		Yes		Yes		Yes		Yes		Yes	