

1355 Capital Blvd. • P.O. Box 30013 • Reno, NV 89520-3013
P 775.834.8080 • F 775.834.8003

Addendum No. 4

Highland Reservoir Cover and Liner Replacement Project

PWP Bid No. WA-2014-306
September 19, 2014

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule have changed per Addendum No. 1.

SPECIFICATION REVISIONS AND DRAWING ATTACHMENTS

SPECIFICATION REVISIONS

The specifications listed below are to be revised to read as follows:

Section 02776, 3.04, F replace text to read:

F. Destructive Testing of Field Seams During Field Installation:

1. The Contractor shall provide and have tested, by a GRI-certified independent laboratory, samples of panel-to-panel field seams taken from field installed panels.
2. One test sample per 500 feet of panel-to-panel field seam shall be tested for the above tests (peel strength, breakaway peel strength, and tensile strength).
3. Certified test results of specimens from each sample shall be submitted to the Engineer for review and approval.
4. If any test results are not satisfactory, TMWA, at their discretion, may require that additional sampling and testing be done at the Contractor expense.

Section 02778, 3.04, F replace text to read:

F. Destructive Testing of Field Seams During Field Installation:

1. The Contractor shall provide and have tested, by a GRI-certified independent laboratory, samples of panel-to-panel field seams taken from field installed panels.
2. One test sample per 500 feet of panel-to-panel field seam shall be tested for the above tests (peel strength, breakaway peel strength, and tensile strength).
3. Certified test results of specimens from each sample shall be submitted to the Engineer for review and approval.
4. If any test results are not satisfactory, TMWA, at their discretion, may require that additional sampling and testing be done at the Contractor expense.

DRAWINGS

There were some revised drawings which were stated as part of Addendum #3 but not included as attachments. These drawings are listed below and attached hereto.

- C-204
- C-205
- C-328