

1355 Capital Blvd. • P.O. Box 30013 • Reno, NV 89520-3013
P 775.834.8080 • F 775.834.8003

Addendum No. 3

Donner Dam Ph 2 Repairs

TMWA Bid No. 2017-003
November 28, 2016

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

Questions and Responses

Question No. 1: The anticipated start date for the project is December 14, 2016 and the temperatures for the project location is well below the manufactures recommendations for the repairs of the Dam, the Aesthetic Coating and, Deck Repair/Overlay which are all of Cement based products. By completing this work in the temperatures during this time is subject to improper curing of the new repairs and overlay as well as the finish coat of the dam when the repairs are completed. Even if the contractor completely tented the dam and used heaters the freeze thaw of the work after it was placed could cause the work to fail.

We request that the start date for the work be postponed until the temperatures are within the requirements of the products specified for the project.

Response to Question No. 1:

The contract dates for the project shall be modified such that the issuance of the Notice to Proceed shall be January 4th, 2017 and the project completion date shall be April 21, 2017.

Question No. 2: Bid item 9 Misc. Rock Pockets and Spalls: is a lump sum item and there is no call out on the plans where our how much there is for this item.

We request that the TMWA supply a quantity by the square foot for this item.

Response to Question No. 2:

The location of the rock pockets is in the soffit of the middle channel as shown on 2/S3. Contractors are directed to modify Bid Item No. 9 to reflect a quantity and unit of 30 square feet.