

## Bid Tabulation Report - BIG KNOB BOOSTER PUMP STATION

			Bidder No. 1		Bidder No. 2		Bidder No. 3	
			K.G. Walters Construction Co., Inc.		Gerhardt & Berry Construction, Inc.		Farr Construction Corporation dba Resource Development Company	
Bonding Provided			Yes		Yes		Yes	
Bidder Acknowledges Receipt of Addendums			Yes		Yes		Yes	
Affidavit of Preferential Bidders Status / Bidder's Preference Certificate			Yes		Yes		Yes	
Description	Scheduled	Unit	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
	Value							
<b>1. Mobilization, Insurance, Bonds, Permits, Site Clean-Up, Demobilization, and Miscellaneous Fees.</b>	1	LS	\$25,000.00	\$25,000.00	\$19,239.00	\$19,239.00	\$39,000.00	\$39,000.00
<b>2. Furnish and Install Traffic Control.</b>	1	LS	\$6,000.00	\$6,000.00	\$5,321.80	\$5,321.80	\$31,000.00	\$31,000.00
<b>3. Furnish and Install Restrained 6-inch Diameter Pressure Class 350 Ductile Iron Water Main.</b> This item includes trenching, bedding, pipe, fittings, couplers, valves (including air-release valves), thrust blocks/pads, all required appurtenances, backfill, compaction, temporary asphalt patching, permanent asphalt patching of trench and other areas as required by the Washoe County Permit, permanent asphalt patching testing, and flushing required for completion as depicted in the Improvement Plans.	260	LF	\$310.00	\$80,600.00	\$300.00	\$78,000.00	\$620.00	\$161,200.00
<b>4. Fire Hydrant Assembly.</b> This item includes the installation of new fire hydrant assembly, trenching, bedding, 6" Diameter Pressure Class 235 C900 PVC lateral piping, thrust blocks/pads, valves and fittings, backfill, compaction, temporary asphalt patching, permanent asphalt patching of trench and other areas as required by the Washoe County Permit, permanent asphalt patching testing, red curb paint, and all required appurtenances for completion as depicted in the Improvement Plans.	1	EA	\$7,500.00	\$7,500.00	\$9,425.00	\$9,425.00	\$16,000.00	\$16,000.00
<b>5. Furnish and Install 2-inch Diameter HDPE Water Line.</b> This item includes excavation, bedding, pipe, fittings, couplers, valves, thrust blocks/pads, all required appurtenances, backfill, compaction, temporary asphalt patching, permanent asphalt patching of trench and other areas as required by the Washoe County Permit, permanent asphalt patching testing, and flushing required for completion as depicted in the Improvement Plans.	215	LF	\$50.00	\$10,750.00	\$39.75	\$8,546.25	\$175.00	\$37,625.00
<b>6. Furnish and Install 2-inch Air Release Valve Assembly.</b> This item includes trenching, all required appurtenances, backfill, compaction, as depicted in the Improvement Plans.	2	EA	\$4,000.00	\$8,000.00	\$3,666.00	\$7,332.00	\$6,700.00	\$13,400.00
<b>7. Furnish and Install Booster Pump Station Cans, Pumps, and Assembly.</b> This item includes excavation, two submersible pumps with motors, two 8" diameter fabricated pump cans, manifold fittings, connection piping, all required appurtenances, backfill, compaction, testing and startup, as depicted in the Improvement Plans.	1	LS	\$130,000.00	\$130,000.00	\$127,794.00	\$127,794.00	\$149,000.00	\$149,000.00

