

Addendum No. 3

STMGID ARROWCREEK BPS MAIN

PWP Bid No.: WA-2018-157
TMWA Capital Project No.: 50-0001.08
April 19, 2018

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

CLARIFICATION

Clarification Item No 1: Please replace page 4 of the Bid Schedule. The changes include the adjustment of the following Bid Items:

- Bid Item 4: Quantity has been revised from 716 LF to 410 LF.
- Bid Item 5: Quantity has been revised from 1510 LF to 1816 LF.
- Bid Item 7: Quantity has been revised from 3 EA to 4 EA

QUESTION CUT-OFF DATE: April 18, 2018
END OF ADDENDUM NO. 3

**ATTACHMENT “A”
REVISED BID SCHEDULE PAGE 4
DATED 4-19-18**

BID SCHEDULES
(Cont)

Description	Scheduled Value	Unit	Unit Price	Total Price
2. 16-in CL 250 Polywrapped Ductile Iron Pipe w/unrestrained joints. Including all saw cutting, concrete removal, excavation, off-haul, bedding, backfill and traffic control as necessary for a complete in-place installation.	4778	LF		
3. 16-in CL 250 Polywrapped Ductile Iron Pipe w/restrained joints. Including all saw cutting, concrete removal, excavation, off-haul, bedding, backfill and traffic control as necessary for a complete in-place installation.	1102	LF		
4. 16-in CL 300 Polywrapped Ductile Iron Pipe w/ restrained unrestrained joints. Including all saw cutting, concrete removal, excavation, off-haul, bedding, backfill and traffic control as necessary for a complete in-place installation.	716 410	LF		
5. 16-in CL 300 Polywrapped Ductile Iron Pipe w/restrained joints. Including all saw cutting, concrete removal, excavation, off-haul, bedding, backfill and traffic control as necessary for a complete in-place installation.	1510 1816	LF		
6. Linestop installation per Detail 6/D4	1	EA		
7. Installation of 4-in Air/Vac Assembly per Detail 1/D3	3 4	EA		
8. Install of 2-in Service Saddle Flush Assembly per Detail 2/D2	6	EA		
9. Installation of Connection Detail 1/D4	1	EA		
10. Installation of Connection Detail 2/D4	1	EA		
11. Concrete Curb per Detail 4/D1	3204	LF		
12. Concrete Curb & Gutter per Detail 3/D1	1094	LF		
13. Concrete Curb & Gutter per Detail R-109/D5	8	LF		
14. 4 ft wide Concrete Sidewalk per Detail 5/D1	288	SF		
15. 5 ft wide Concrete Sidewalk per Detail 5/D1	1935	SF		
16. 4 ft wide Concrete Sidewalk per Detail R-104A/D5	32	SF		
17. Tee & Valve per Detail 3/D2	1	EA		
18. Concrete Driveway Entrance	1	EA		
19. Temporary A.C. Patch - Washoe County R.O.W.	2480	SF		