

1355 Capital Blvd. • P.O. Box 30013 • Reno, NV 89520-3013
P 775.834.8080 • F 775.834.8003

Addendum No. 2

TMWA 4th STREET SITE IMPROVEMENTS PROJECT

PWP Bid No. WA-2015-187
June 2, 2015

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

QUESTIONS AND RESPONSES

Question No. 1: Per Bid Item #11-Remove Existing SS Cleanout & Lateral; does TMWA know the what type of pipe material was used (i.e. AC pipe)? If the existing sewer lateral is AC pipe, how is it to be disposed of?

Response to Question No. 1: It is unknown what type of pipe material was used for the existing SS laterals. If the existing sewer lateral is AC pipe, removal will require an Acknowledgement of Asbestos Assessment Permit through the Washoe County Health Department's Air Quality Management Division. If a permit is required, the Contractor will be responsible for obtaining the permit and paying the required fee(s). (Reference Attachment 3 of the Technical Specifications for an example of the required permit). The material shall be removed and disposed of using Best Work Practices and the Contractor will be required to have proper asbestos training to complete the work.

Question No. 2: Per Plan Note #31 on sheet C2.0 it states "Existing Water Meter Box- Cut and Cap Pipe on Discharge side of Meter Setter" In which bid item should these costs be included in?

Response to Question No. 2: On bid schedule item No. 9, add the following item description, "Cut and Cap Pipe on discharge side of meter setter per plan key note No. 31." Change quantities on bid schedule item 9 from 2 EA to 3 EA.