

			Bidder No. 1		Bidder No. 2		Bidder No. 3	
			Gerhardt & Berry Construction, Inc.		MKD Construction, Inc.		Spanish Springs Construction, Inc.	
Bonding Provided			Yes		Yes		Yes	
Bidder Acknowledges Receipt of Addendums			Yes		Yes		Yes	
Affadivit of Preferential Bidders Status / Bidder's Preference Certificate			Yes		Yes Affidavit/No certificate		Yes	
Description	Scheduled	Unit	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
	Value							
<b>1. Mobilization, Insurance, Bonds, Permits, Site Clean-Up, Demobilization, and Miscellaneous Fees.</b>	1	LS	14,050.00	14,050.00	37,000.00	37,000.00	35,194.00	35,194.00
<b>2. Furnish and Install Traffic Control</b>	1	LS	18,150.00	18,150.00	56,900.00	56,900.00	50,000.00	50,000.00
<b>3. Spot Repair at 2195 Mill St/E. 2nd St (Detail 2/D3):</b> Furnish and install restrained joint 12-inch diameter Pressure Class 350 Ductile Iron Water Main and replace existing 6-inch transite service within right-of-way with restrained 6-inch diameter Pressure Class 350 Ductile Iron Pipe. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), all required appurtenances, backfill, compaction, asphalt patching, curb/gutter, sidewalk and driveway patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	19,700.00	19,700.00	20,400.00	20,400.00	32,000.00	32,000.00
<b>4. Spot Repair at 2500 E. 2nd St (Detail 1/D4):</b> Furnish and install restrained joint 12-inch diameter Pressure Class 350 Ductile Iron Water Main and retire existing service lines. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	14,700.00	14,700.00	15,800.00	15,800.00	22,000.00	22,000.00
<b>5. Spot Repair at 2255 Glendale Ave (Detail 2/D4):</b> Furnish and install restrained joint 12-inch diameter Pressure Class 350 Ductile Iron Water Main and retire several existing service lines. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), connection of new 2-inch HDPE service, all required appurtenances, backfill, compaction, asphalt patching, curb/gutter, sidewalk and driveway patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	15,500.00	15,500.00	15,300.00	15,300.00	19,000.00	19,000.00
<b>6. Spot Repair at S Rock Blvd/Glendale Ave (Detail 1/D6):</b> Furnish and install restrained joint 8-inch and 6-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	37,100.00	37,100.00	37,600.00	37,600.00	48,000.00	48,000.00
<b>7. Spot Repair at S Rock Blvd/Glendale Ave (Detail 2/D6):</b> Furnish and install restrained joint 6-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, curb/gutter, sidewalk, and driveway patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	15,100.00	15,100.00	15,300.00	15,300.00	28,000.00	28,000.00
<b>8. Spot Repair at S 15th/ Glendale Ave (Detail 1/D7):</b> Furnish and install restrained joint 12-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	22,715.00	22,715.00	23,700.00	23,700.00	35,000.00	35,000.00
<b>9. Spot Repair at 1506 Glendale Ave (Detail 2/D7):</b> Furnish and install restrained joint 12-inch and 6-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, connection of new 1-inch HDPE service, all required appurtenances, backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	16,495.00	16,495.00	17,600.00	17,600.00	31,000.00	31,000.00
<b>10. Spot Repair at 1500 Glendale (Detail 3/D7):</b> Furnish and install restrained joint 12-inch and 6-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	15,939.00	15,939.00	16,500.00	16,500.00	23,000.00	23,000.00

			Bidder No. 1		Bidder No. 2		Bidder No. 3	
			Gerhardt & Berry Construction, Inc.		MKD Construction, Inc.		Spanish Springs Construction, Inc.	
<b>11. Spot Repair at 1500 Glendale Ave (Detail 1/D8):</b> Furnish and install restrained joint 12-inch and 6-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	15,819.00	15,819.00	17,400.00	17,400.00	23,000.00	23,000.00
<b>12. Spot Repair at 1484 Glendale Ave (Detail 2/D8):</b> Furnish and install restrained joint 12-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	18,495.00	18,495.00	18,800.00	18,800.00	30,000.00	30,000.00
<b>13. Main Retirement:</b> Remove and dispose existing 8-inch to 12-inch diameter transite or cast iron water main, including trenching; removal and disposal of existing improvements regardless of material; bedding; appurtenances; capping existing main as required; backfill; compaction; and asphalt patching required for completion as depicted in the Improvement Plans.	905	LF	75.00	67,875.00	45.00	40,725.00	120.00	108,600.00
<b>14. Raise Existing Valve:</b> Raise existing valve with new conductor and valve box, including excavation, removal, and disposal of existing improvements regardless of material, furnishing and installing new conductor pipe and valve box, backfill, compaction, asphalt patching, and all incidentals required for completion as depicted in the Improvement Plans.	3	EA	1,075.00	3,225.00	950.00	2,850.00	550.00	1,650.00
<b>15. Service Relocation:</b> Furnish and install service relocation, including trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves backfill, compaction, asphalt patching, testing, and flushing required for completion as depicted in the Improvement Plans.	2	EA	1,798.00	3,596.00	2,300.00	4,600.00	10,000.00	20,000.00
<b>16. Verify Service Retirement:</b> Pothole at the locations indicated on the Improvement Plans and verify whether service was retired correctly per TMWA requirements, including excavation to expose existing services to determine retirement, bedding, backfill, compaction, asphalt patching, and all incidentals required for completion as depicted in the Improvement Plans. If service was not retired correctly per TMWA requirements, the Contractor shall retire the service at the main per TMWA requirements (NDP).	6	EA	1,442.00	8,652.00	2,700.00	16,200.00	4,000.00	24,000.00
<b>17. *Spot Repair at 2050 Glendale Ave (Detail 1/D5):</b> Replace existing with restrained joint 6-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, curb/gutter, sidewalk, and driveway patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	20,359.00	20,359.00	21,400.00	21,400.00	41,000.00	41,000.00
<b>18. *Spot Repair at 600 Glendale Ave (Detail 2/D5):</b> Replace existing with restrained joint 6-inch and 12-inch diameter Pressure Class 350 Ductile Iron Water Main. This item includes trenching, removal and disposal of existing improvements regardless of material, bedding, pipe, fittings, couplers, valves (including gate valves), thrust blocks/pads, all required appurtenances, backfill, compaction, asphalt patching, curb/gutter, sidewalk, and driveway patching, testing, and flushing required for completion as depicted in the Improvement Plans.	1	EA	19,143.00	19,143.00	18,900.00	18,900.00	41,000.00	41,000.00
<b>Total Bid Price</b>				<b>\$346,613.00</b>		<b>\$396,975.00</b>		<b>\$612,444.00</b>
<b>Total Bid Price Written in Words? y/n</b>				Yes		Yes		Yes
<b>Bidder Information Provided</b>				Yes		Yes		Yes
<b>Licensing Information Provided</b>				Yes		Yes		Yes
<b>Disclosure of Principals Provided</b>				Yes		Yes		Yes
<b>Referenced Provided</b>				Yes		Yes		Yes
<b>Debarment &amp; Safety Information Provided</b>				Yes		Yes		Yes
<b>Subcontractors Listed / Self Listed</b>				Yes		Yes		Yes
<b>Proposal Summary Executed</b>				Yes		Yes		Yes