

1355 Capital Blvd. • P.O. Box 30013 • Reno, NV 89520-3013
P 775.834.8080 • F 775.834.8003

Addendum No. 1

CHALK BLUFF SOLIDS STORAGE POND 2

PWP Bid No. WA-2016-259
September 23, 2016

The following information, clarifications, changes and modifications are by reference incorporated into the bid documents for the above referenced project. Any work item or contract provision not changed or modified will remain in full force and effect. The bid date and time and construction schedule remain the same.

Clarification: The following notes shall be added to the call-out for the 24-in culvert shown on Sheet C2 of the Drawings:

The CMP culvert shall be 24-in diameter, 12 ga minimum thickness with aluminized coating. Product shall be Contech Hel-Cor CMP or approved equal. Trench details, bedding materials and compaction requirements shall be per TMWA's standards. Bedding shall be compacted to 90% of M.D.D. Backfill will be as per the requirements for embankment provided on the Drawings.

Question No. 1: Will construction water be available on site for this project?

Response to Question No.: Water, for dust control and general project operations, will be available via the Highland Canal at the location shown on the figure below. The contractor shall be responsible for providing their own equipment to pump water from the canal into their water trucks. This shall include suction and discharge piping, intake screening (if necessary), pumps and power supplies. There will be no additional pay item for the construction water this and this will be considered incidental to the overall project work.

